

PLANNING BOARD
TOWN OF BETHLEHEM
ALBANY COUNTY, NEW YORK
By direction of the Chairman.
These drawings are hereby approved.
See sheet(s) 3, 6, 7
for date and signature.

BETHLEHEM PLANNING BOARD APPROVAL

CONSTRUCTION SEQUENCE (EXCAVATION & ROADWAY CONSTRUCTION):

1. ESTABLISH PERIMETER SILT FENCING, WETLAND BARRIERS, AND STABILIZED CONSTRUCTION ENTRANCES FOR THE PHASE TO BE DISTURBED.
2. CONSTRUCT HAUL ROADS AND ACCESS ROADS TO DETENTION PONDS.
3. CONSTRUCT DETENTION PONDS
4. CONSTRUCT OUTLET STRUCTURE WITHIN THE SEDIMENT TRAP OR DETENTION POND TO ALLOW FUNCTIONALITY AS A TEMPORARY SEDIMENT BASIN DURING SITE CONSTRUCTION.
5. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THEIR TRIBUTARY AREAS.
6. BEGIN ROUGH GRADING OF ROADWAY ALIGNMENTS, TAKING CARE TO ESTABLISH ANY SWALES WITH TEMPORARY CHECK DAMS TO DIVERT RUNOFF TO STORM SEWER; STABILIZE CUT AND FILL SLOPES, STABILIZE INTERNAL ROADWAY AREAS WITH SUBBASE COURSE AS NECESSARY.
7. INSTALL SEWER LINES, STORM DRAINAGE SYSTEM AND WATER LINES. INSTALL DROP INLET SEDIMENT TRAPS AND CHECK DAMS IN DRAINAGE FLOW LINES.
8. COMPLETE SUBGRADE EXCAVATION, CONSTRUCT BASE COURSE, STABILIZE WITH SUB ROADWAY.
9. INSTALL ADDITIONAL SILT FENCING AS NEEDED AS CLEARING AND GRADING ACTIVITIES PROGRESS.
10. UPON COMPLETION OF RIGHT OF WAY GRADING, TEMPORARY SEEDING AND ESTABLISHMENT OF VEGETATIVE COVER SHALL OCCUR.
11. INSTALL BITUMINOUS PAVEMENT FOR ALL NEW ROADWAYS.
12. PRIOR TO FINALIZING CONNECTION TO THE STORM SEWER SYSTEM, ALL CATCH BASINS AND DRAINAGE LINES SHALL BE CLEANED OF ALL SILT AND SEDIMENT.
13. CONTRACTOR SHALL IMMEDIATELY ESTABLISH PERMANENT VEGETATION ON ALL DISTURBED AREAS. ONCE FINAL STABILIZATION IS ACHIEVED REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES.
19. REMOVE ALL SEDIMENT AND TEMPORARY SEDIMENT BASIN COMPONENTS FROM THE SEDIMENT BASIN.
20. CONTINUE INSPECTION AND MAINTENANCE OF ROADWAY, EROSION/SEDIMENT CONTROL DEVICES AND POST-CONSTRUCTION MANAGEMENT PRACTICES THROUGHOUT THE DURATION OF THE CONSTRUCTION.

CONSTRUCTION SEQUENCE (INDIVIDUAL LOT CONSTRUCTION):

1. SILT FENCING SHALL BE INSTALLED ALONG ROADWAY TO PREVENT SEDIMENT FROM ENTERING THE CLOSED DRAINAGE NETWORK WITHIN THE ROADWAY.
2. INSTALL STABILIZED CONSTRUCTION ENTRANCE PRIOR TO ANY LOT DISTURBANCE.
3. COMPLETE EXCAVATION, GRADING IN BUILDING AREA AND CONSTRUCT PROPERTY LINE SWALES.
4. STABILIZE GRADED AREAS AND SWALES WITH SEED AND MULCH INCLUDING EROSION MATTING AND TEMPORARY CHECK DAMS AS NECESSARY TO PREVENT EROSION.
5. CONTINUE INSPECTION AND MAINTENANCE OF THE INDIVIDUAL LOT UNTIL FINAL STABILIZATION IS ACHIEVED.

EROSION CONTROL GENERAL NOTES:

1. THIS PROJECT IS AUTHORIZED UNDER NYSDEC PERMIT GP-0-15-002.
2. ANY CONTRACTOR INVOLVED IN EARTHWORK ACTIVITIES, INCLUDING BUT NOT LIMITED TO: CLEARING, GRADING AND TRENCHING, SHALL REVIEW ALL PERMIT CONDITIONS AND CERTIFY UNDERSTANDING OF THESE CONDITIONS, IN WRITING. IT IS THE CONTRACTOR'S RESPONSIBILITY TO IMPLEMENT ALL EROSION CONTROLS DESCRIBED IN GP-0-15-002, AND IT IS NOT THE INTENT OF THESE DRAWINGS TO REPLACE OR DISSEMINATE THE PERMIT REQUIREMENTS. THE CONTRACTOR SHALL REMAIN IN COMPLIANCE WITH THE PERMIT AT ALL TIMES.
3. AT NO TIME, SHALL MORE THAN FIVE (5) ACRES REMAIN UNSTABILIZED. THE CONTRACTOR SHALL COORDINATE EARTHWORK ACTIVITIES AND IMPLEMENTATION OF SOIL STABILIZATION MEASURES TO ENSURE COMPLIANCE TO THIS PERMIT REQUIREMENT.
4. THE CONTRACTOR SHALL MAINTAIN A CLEAN CONSTRUCTION AND EQUIPMENT ENTRANCE WHENEVER PRACTICABLE.
5. DISTURBED AREAS SHALL BE STABILIZED WITHIN 14 DAYS OF COMPLETION OR SUSPENSION OF GRADING OPERATIONS.
6. A NOTICE OF INTENT (NOI) MUST BE FILED WITH THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION FIVE (5) BUSINESS DAYS PRIOR TO CONSTRUCTION ACTIVITIES WHICH DISTURB MORE THAN ONE ACRE OF LAND AFFIRMING THAT A STORMWATER POLLUTION PREVENTION PLAN HAS BEEN PREPARED CONSISTENT WITH THE REQUIREMENTS INCLUDED IN THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION SPDES GENERAL PERMIT FOR STORMWATER DISCHARGES (GP-0-15-002).
7. NO TOPSOIL SHALL BE REMOVED FROM ANY LAND EXCEPT WHERE HEAVY EQUIPMENT WILL BE OPERATED. IN THESE AREAS TOPSOIL SHALL BE STRIPPED AND STOCKPILED ON THE PROPERTY FOR REPLACEMENT AT THE COMPLETION OF CONSTRUCTION.




TOWN OF BETHLEHEM, NEW YORK
PLANNING DEPT. ORIGINAL
- SCANNED -

ALBANY COUNTY DEPARTMENT OF HEALTH
DIVISION OF ENVIRONMENTAL HEALTH SERVICES

by direction of the Commissioner of Health, these
plans are hereby approved. See first sheet for
date and signature.

| | | | | |
|-----|----------|---------------------------------|-----|---|
| | | | | UNAUTHORIZED ALTERATION OR ADDITION TO THIS DRAWING IS A VIOLATION OF SECTION 7209 SUBDIVISION 2, OF THE NEW YORK STATE EDUCATION LAW. ONLY COPIES MADE FROM THE ORIGINAL OF THIS DRAWING BEARING AN ORIGINAL INKED OR EMBOSSED SEAL AND SIGNATURE SHALL BE CONSIDERED TO BE VALID TRUE COPIES. |
| 6 | 11/16/15 | REVISED PER TOWN COMMENTS | PJY | |
| 5 | 10/6/15 | REVISED PER TOWN COMMENTS | PJY | |
| 4 | 8/13/15 | REVISED PER TOWN & TDE COMMENTS | PJY | |
| 3 | 6/19/15 | REVISED PER TOWN & TDE COMMENTS | PJY | |
| 2 | 3/5/15 | REVISED PER TOWN & TDE COMMENTS | PJY | |
| 1 | 9/23/14 | REVISED PER TOWN & TDE COMMENTS | PJY | |
| NO. | DATE: | REVISIONS | BY: | © Copyright 2015 - Ingalls & Associates, LLP - All rights reserved |



ingalls

ingalls & associates, LLC
engineering, environmental, surveying

E&SC PLAN 1
NEWELL PLACE
WEMPLE ROAD

TOWN OF BETHLEHEM
NY COUNTY STATE OF NEW YORK

38DF SHEET 18 OF 20